



Program	Production capacity increase Project in Locomotive Manufacturing company
Date Completed	5 th February 2016
Scope	Production Capacity Increase
KEY ACTIVITIES	 Reviewed AS-IS production layout~ 2500 to3000 parts. TO-BE production line decomposed into nine cellular layouts Completed SimCAD Simulation on TO-BE layout to eliminate bottle necks, improve line balancing and material work follow Interviewed all section managers over a three-week period to ensure buy in onboarding Identified Key equipment ~ commissioning and installation. Design, development and manufacture of special tools, jigs and fixtures. Implemented all works instructions, stand operating procedures.
FINDINGS AND	8. Excess overtime.9. Production capacity limited to below 52 locomotives per year.10. Dis-organised work flows
OUTCOMES	11. Cluttered works areas. 12. No works area definitions
	 No clear defined work in-progress segregation areas Wasted man hours due to personnel standing waiting for an assembly process to be completed. Materials and work in-progress spread through the factory. Poor house keeping.
IMPROVEMENTS	17. Increased manufacturing capacity from 52 Locomotives per year to 106
AND	locomotives per year 18. Eliminated overtime
RECOMMENDATIONS	 19. Implemented designated work bays a. Created work stations for the different process steps. b. Introduced buffer stations for in complete equipment supply or quality problems 20. Improved offline process work areas 21. Improved House keeping 22. Online job carding 23. Online process quality control checking 24. Conduct Time studies
FURTHER OPPORTUNITIES	25. Implement a functional Quality Management system.26. Implement Time standards.27. Production Line performance metrics.28. Insourcing rather than out sourcing of fabricated components.





